Year: In progress
Location: Pakistan
Program: School, Temporary Housing

2022 Pakistan floods Disaster Relief Project

As a relief effort for the Pakistan floods that occurred in the summer of 2022, plans for low-cost housing and building paper schools are in progress in collaboration with a local organization, Safe Delivery Safe Mother.

Phase1
low-cost housing

Phase2
low-cost housing

Phase3
schools

Phase3 : <Paper School> January 2026

In Dadu, Sindh Province, Pakistan, we constructed two schools. The walls are finished with strips of bamboo fixed to paper tube frames, which also serve a structural role as bracing. The roofs are thatched with locally sourced straw, helping to keep the interior from becoming too hot in summer.
Local partner: Safe Delivery Safe Mother

1. Opening Ceremony of the Elementary School in Lal Bux Naich, Dadu District, Sindh Province

2. Opening Ceremony of the Elementary School in Ali Sher Shaikb, Dadu District, Sindh Province

Phase2 : <Low-Cost Housing> Pilot Project March 2025

At March 2025, We have successfully completed the construction of two PLH structures as per our revised design and discussions in Dadu district of the Sindh province and handed over to the two selected families. This district is one of the worst affected districts from the 2022 floods.

Phase2 : <Low-Cost Housing> First Prototype April 2024

The first prototype was completed in April 2024. A pilot project of 10 to 20 houses is planned for the second phase.